

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO 12-0092-4

FOR: SHIPYARD ROAD - LEHIGH AVENUE DRAINAGE IMPROVEMENTS

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

NOTE: REPLACE CURRENT BID SHEET WITH THE ATTACHED *REVISED* BID SHEET

Questions regarding incorrect Units of Measure on the current Bid Sheets have been answered by this Bid Sheet Revision.

Questions Received:

1. Will we be able to do a shutdown of the existing Water Line every time we need to do the work as shown on the plans? Who is the owner of the Water Line?

The existing water line is owned by Chatham County. It can be shutdown for relocations.

2. Sheet 03 *Relocate Force Main as Required to Avoid Conflict with Storm Drain*

A. Will we be able to shutdown the pump station?

B. What size is the existing Force Main?

C. Do you know approximately how much of the Force Main will need to be relocated?

D. Who is the owner of the pump station and Force Main?

The Force Main comes from a small grinder pump serving the parcel on the corner. It is a small diameter PVC pipe. It is privately owned by the resident. As to the extent of relocation, staff is unsure.

3. Sheet 12 *Trench Section Detail* - It calls for the Elliptical Pipe bedding to be flowable fill. Is this required on this job?

For this job, assume it is to be flowable fill.

4. Section 01600-5 *Post Construction Inspection* - It calls for the Storm Lines to be video inspected provided on a standard DVD and compatible with County viewing software. What viewing software does the County use?

The County has the standard capabilities for software viewing. If you can view it on Windows Media Player or Roxio, it is acceptable.

THE BID OPENING REMAINS :

2PM, THURSDAY, SEPTEMBER 20, 2012.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

9-14-12
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

BID SHEET

Shipyards Lehigh Drainage Improvements
Chatham County, Georgia

14-Sep-12

Item #	Description	Estim. Qty.	Unit Price	Total Price
1	Grading, complete, including all project excavation/filling, finish grading, clearing, grubbing and all other removals not specifically listed, bonds, insurance and other project incidentals	1	LS	
2	Remove unsuitable subgrade material	200	CY	
3	Foreign Borrow - Replace unsuitable subgrade or trench material only where directed by owner	400	CY	
4	14"x23" Concrete Elliptical Pipe	92	LF	
5	18" Storm Drain Pipe	386	LF	
6	24" Storm Drain Pipe	320	LF	
7	30" Storm Drain Pipe	46	LF	
8	36" Storm Drain Pipe	124	LF	
9	42" Storm Drain Pipe	110	LF	
10	18" Flared End Section	12	EA	
11	24" Flared End Section	6	EA	
12	30" Flared End Section	1	EA	
13	36" Flared End Section	3	EA	
14	42" Flared End Section	2	EA	
15	Stone for Bedding	100	CY	
16	Grate Inlet	2	EA	
17	Storm Manhole, 48" diameter	2	EA	
18	Storm Manhole, 60" diameter	1	SY	
19	Storm Manhole, 72" diameter	2	EA	
20	Concrete Swale, 4" Thickness	10	SY	
21	20' Chain Link Gate, 4' Height	1	EA	
22	Remove and Replace Sidewalk	4	SY	
23	Remove and Replace Asphalt Pavement	300	SY	
24	Remove and Replace Asphalt Drive	25	SY	
25	Remove and Replace Concrete Drive	50	SY	
26	Remove and Reset Mailbox	12	EA	
27	Remove and Reset Signs	6	EA	
28	6" Valve in Manhole	1	EA	
29	Utility Coordination and Relocations	1	LS	
30	Rip-Rap, including filter fabric, St	150	SY	
31	Traffic Control	1	LS	
32	Grassing	10,000	SY	
33	Haybale Check Dam, Cd	33	EA	
34	Silt Fence, Sd1-A	1,420	LF	
35	Silt Fence, Sd2-F	2	EA	
36	Field Allowance	1	LS	20,000.00

TOTAL

NAME/ TITLE

COMPANY

ADDRESS

PHONE / FAX NO'S.

EMAIL