

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO Bid No. 12-0103-7

**FOR: Street Resurfacing at Various Locations within Chatham County**

---

**PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES:**

1. **Question: What warranty requirements apply to this project and is a separate price required?**

**Answer: Refer to Section 4.4.2, Contractor shall fully warrant materials and workmanship for a period of two (2) years from date of acceptance by the Chatham County Public Works Department Project Manager. The price of the warranty should be included in the bid price.**

2. **Question: Is temporary striping going to be required?**

**Answer: Yes, temporary striping will be required.**

3. **Will the County entertain adding a bid item for Bituminous Tack Coat by the gallon as per GDOT specifications?**

**Answer: No**

4. **Will any asphalt patching be required?**

**Answer: No, the Contractor will not be required to provide asphalt patching.**

5. **Question: Reference Section 4.2.5, Please define and clarify what will be required for storm water pollution prevention, shoulder repair and unsuitable material removal. How will this additional work be paid?**

**Answer: Storm water pollution prevention shall include blocking inlets if prep work prior to laying asphalt will result in soil washing into the storm drain system. If a contractor in the process of turning back overgrowth from the road way in order to get to the edge of pavement should damage the shoulder, the contractor is responsible to repair the shoulder or if the contractor damages the shoulder due to equipment being parked on the shoulder they are responsible to repair. Unsuitable material is excess asphalt, binder or concrete poured on the ROW or overgrowth from turning back grass/weeds to uncover the edge of pavement. The County does not consider this additional work.**

6. **The bid states that the completion date will be 45 calendar days after notice to proceed. GDOT asphalt temperature specification for 1.25" of asphalt is 45 degrees and rising. With the weather limitations and holiday restriction for November, December and January, will the County entertain the NTP to be issued after March 1, 2013/or change**

the completion date?

**Answer:** The completion days has been changed from 45 days to 90 days.

7. **Question:** What reference format is required?

**Answer:** Please use the format that is specified in the bid package in Section 2.30.

8. **Question:** Will the County entertain changing the unit of measure for mobilization to lump sum.

**Answer:** Yes, please see revised bid sheet.

9. **Question:** Will the County entertain allowing the Form D-2 for subcontractors to be executed and submitted after award of contract to the successful bidder?

**Answer:** The Contractor is not required to submit Form D-2 with their bid package, but must provide the form prior to execution of contract.

10. **Question:** Please provide verification on quantities for Quarterman Drive and Tropical Way?

**Answer:** The quantities have been verified and stand as previously stated. Please see revised bid sheet which has changed from "Quarterman Drive - Tropical Way to Johnny Mercer" to "Quarterman Drive - Golden Isles to Johnny Mercer"

11. It appears that on at least Bryan Woods Road, there will be some thermo hatching that will need to be replaced, but there is no bid item for that work. Will the hatching be replaced after resurfacing? If so, could you please add a bid item for hatching?

**Answer:** The 20,000 LF of Yellow Solid includes the cross hatching.

12. Under Wilmington Island Road there is a bid item for Yellow Stripe Thermo; Is this supposed to be Yellow Skip Thermo?

**Answer:** Yes, please see revised bid sheet.

13. Will the County entertain using a spread rate as per GDOT in lieu of 1.25" of 9.5MM?

**Answer:** Yes

14. Is this project part on the LMIG funding the GDOT is now allowing the local Municipalities to bid in lieu of the GDOT Lau/Lar projects?

**Answer:** No, this is a local project and GDOT is not associated.

15. Please clarify if the leveling quantity is to be calculated by taking all the asphalt tickets

for a particular road and subtracting theoretical rate of 135#/per sy from the total tons.  
The remaining tons will be paid as leveling.

Answer: Yes, with Public Works Representative concurrence.

16. CHANGE: A revised bid sheet is attached and is to be used when submitting bid.

---

---


**THE BID OPENING SHALL REMAIN 2PM NOVEMBER 8,  
2012.**

---

---

**THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND  
MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.**

11-01-12  
DATE

  
MARGARET H. JOYNER  
PURCHASING AGENT  
CHATHAM COUNTY

**REVISED BID SHEET**

**BID NO. 12-0103-7**

**STREET RESURFACING AT VARIOUS LOCATIONS WITHIN CHATHAM COUNTY**

<b>Description</b>	<b>U/M</b>	<b>Qty</b>	<b>Unit Cost</b>	<b>Total Cost</b>
<b>Bryan Woods Road</b>				
Johnny Mercer to US 80	<b>SY</b>	<b>30572</b>		
White Solid Thermo	<b>LF</b>	<b>9740</b>		
Yellow Solid Thermo	<b>LF</b>	<b>20000</b>		
White Skip Thermo	<b>LF</b>	<b>9740</b>		
Crosswalks Thermo	<b>EA</b>	<b>2</b>		
Stop Bars Thermo	<b>EA</b>	<b>2</b>		
Pavement Markings (Arrow) Thermo	<b>EA</b>	<b>19</b>		
Pavement Markings Word (Only) Thermo	<b>EA</b>	<b>2</b>		
<b>Capstan Court</b>				
Crossover Lane to Mapmaker	<b>SY</b>	<b>682</b>		
<b>Dry Dock Court</b>				
Crossover Lane around Circle	<b>SY</b>	<b>1216</b>		
<b>Crossover Lane</b>				
Binnacle Court around Circle	<b>SY</b>	<b>1749</b>		
<b>Brigantine Court</b>				
Commodore Drive around Circle	<b>SY</b>	<b>1074</b>		
<b>Quarterman Drive</b>				
Golden Isles to Johnny Mercer	<b>SY</b>	<b>3168</b>		
White Solid Thermo	<b>LF</b>	<b>2376</b>		
Yellow Skip Thermo	<b>LF</b>	<b>844</b>		
Yellow Solid Thermo	<b>LF</b>	<b>1188</b>		
Stop Bar Thermo	<b>EA</b>	<b>1</b>		

**REVISED BID SHEET**

<b>Description</b>	<b>U/M</b>	<b>Qty</b>	<b>Unit Cost</b>	<b>Total Cost</b>
<b>Overlook Road</b>				
Sandnettlles Drive to Sand Road	<b>SY</b>	<b>2647</b>		
<b>Christie Road</b>				
Sandnettlles Drive to Sand Road	<b>SY</b>	<b>2655</b>		
<b>Donna Road</b>				
Sandnettle Drive to Sand Road	<b>SY</b>	<b>2652</b>		
<b>Debra Road</b>				
Sand Road to End	<b>SY</b>	<b>2481</b>		
<b>Hillary Road</b>				
Sand Road around Circle	<b>SY</b>	<b>2532</b>		
<b>Treasure Loop</b>				
Golden Isles to Tropical Way	<b>SY</b>	<b>1645</b>		
<b>Tropical Way</b>				
Quarterman to Golden Isles Way	<b>SY</b>	<b>5964</b>		
<b>Sugar Tree Court</b>				
Sugar Tree Court to Tropical Way	<b>SY</b>	<b>769</b>		
<b>Nassau Court</b>				
Nassau Drive around Circle	<b>SY</b>	<b>702</b>		
<b>Nassau Drive</b>				
Sea Island Drive to Okatee Drive	<b>SY</b>	<b>3536</b>		
<b>Wellington Road</b>				
Millward around Circle	<b>SY</b>	<b>533</b>		
COS water manhole raised	<b>EA</b>	<b>1</b>		
<b>Cromwell Road</b>				
Biltmore Road to Carlton Road	<b>SY</b>	<b>935</b>		
<b>Brickhaven Road</b>				
Brittlewood Road to Pine Nettle Dr.	<b>SY</b>	<b>2744</b>		

## REVISED BID SHEET

Description	U/M	Qty	Unit Cost	Total Cost
<b>Boxwood Drive</b>				
Walthour Road around circle	SY	3189		
<b>Sheftall Circle North</b>				
Bradford Cove to Penn Waller Road	SY	3504		
<b>Runner Road</b>				
Teakwood Drive to end	SY	1208		
<b>Sandpiper Road</b>				
Bob White around circle	SY	2285		
<b>Talahi Island Place</b>				
Talahi Drive around circle	SY	904		
<b>Key Street</b>				
Howard Foss to Beaumont Drive	SY	1466		
<b>Leary Drive</b>				
Barnett Drive to end	SY	1640		
<b>Noble Glen Drive</b>				
Bluff Drive Diana Drive	SY	4569		
<b>Buckhalter Road</b>				
Hwy 17 to rail road crossing	SY	16378		
White Solid Thermo	LF	12284		
Yellow Solid Thermo	LF	11000		
Yellow Skip Thermo	LF	600		
RR Symbol Thermo	EA	1		
Stop Bar Thermo	EA	1		
<b>Kings Way</b>				
125 LF from Whitefield to Old Montgomery Cross Road	SY	2657		

## REVISED BID SHEET

Description	U/M	Qty	Unit Cost	Total Cost
<b>Wilmington Island Road</b>				
Curve at Golf Course marked by storm drain box and 35 mph	SY	3706		
White Solid Thermo	LF	2780		
Yellow Solid Thermo	LF	4960		
Yellow Skip Thermo	LF	600		
Reflective Road Markers	EA	23		
<b>Mobilization</b>	Lump Sum			
<b>Traffic Control</b>	Lump Sum			
<b>Leveling Tons</b>	TN	500		
			<b>TOTAL BID</b>	<b>\$</b>

\_\_\_\_\_  
NAME/TITLE

\_\_\_\_\_  
COMPANY NAME

\_\_\_\_\_  
ADDRESS

\_\_\_\_\_  
CITY/STATE/ZIP

\_\_\_\_\_  
PHONE NUMBER

\_\_\_\_\_  
FAX NUMBER