

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO.  2  TO  **BID 13-0113-7**

**FOR: Runaway Point Pump Station Upgrade**

---

**PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES:**

1. **CHANGE:** Replace drawing set in its entirety, noting that previous sheets C-6 & C-7 (requirements for locating & pigging forcemain) have been deleted. Other changes to the drawings include, but are not limited to:
  - a. Guy wire location for existing power pole. This guy wire and pole to remain during construction.
  - b. Time requirement for installation of contractor provided temporary by-pass pump.
  - c. Demolition and replacement of wet well concrete top, hatch, and vent
  - d. Revised wooden fence and gate detail with location and size of new gate.
  - e. Location of Contractor lay-down area.
  - f. Temporary removal of overhead power to light fixture.
  - g. Addition of tee with two bypass connections to receive flow from two by-pass pumps at the same time.
  - h. Addition of discharge pressure gauge.
  - i. Regrouting of wet well base as required for warranty of newly installed pumps.
  - j. Relocation of by-pass pump suction line
  
2. **CHANGE:** Replace “Bid Sheet” with revised “Bid Sheet” as part of this document. The Contractor will not be responsible for Force Main Locate and Pigging. This line item has been replaced by “Electrical Complete”. Previous line item 13 “Testing Laboratory Services” has been deleted.
  
3. **CHANGE:** Replace Item 1.04. 9 “Force Main Locate and Pigging” from Technical Specification section 01 20 00 – Price and Payment Procedure in its entirety with the following:
  9. Electrical Complete. Shall include installation of all items associated with sheet E100. This includes pricing from Jay Boudreaux (cell 912-659-6180) for start-up and testing of Alarm Dialer in Section 2.13 of Specification Section 26 00 00 – Electrical Requirements. This does not include Gas Detection Monitor indicated in item 7 of this section.
    - A. Measurement: Measurement shall be by demonstration to Owner and Engineer that above items have been accomplished.

B. Payment shall be in full when measurement has been demonstrated less retainage as required by the contract documents.”

4. **CHANGE:** Delete “Specification Section 32 31 14 – Polyolefin Coated Chain Link Fence Gates and Operator” in its entirety. Refer to revised detail included on sheet C-5 for Wooden Fence and Gate installation details.
5. **CHANGE:** NO alternate shall be allowed for Back Up Self Priming Pump Station indicated in specification section 33 32 13.
6. **CHANGE:** NO alternate shall be allowed for Submersible Wastewater Pump Station indicated in specification section 33 32 16.
7. **CHANGE:** NO alternate shall be allowed for Alarm Dialer indicated in specification section 26 00 00.
8. **CHANGE:** Replace Item 2.06.A “Mounting Frame” from Technical Specification section 33 32 13 – Back Up Self Priming Pump Station in its entirety with the following:
  - A. The complete power unit shall be mounted on a combination frame/single wall fuel tank constructed of tubular steel, with a fuel capacity of 55 US gallons.

**BID DUE DATE REMAINS 2:00PM  
DECEMBER 12, 2013.**


---

---

---

\*\*\*\*\*THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES  
AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.\*\*\*\*\*

12/05/13  
DATE

  
MARGARET H. JOYNER  
PURCHASING AGENT  
CHATHAM COUNTY

**REVISED BID SHEET**

**BID NO. 13-0113-7**

**RUNAWAY POINT PUMP STATION UPGRADE**

| Item No. | Description                                   | U/M | Qty | Unit Cost        | Total Cost |
|----------|---|-----|-----|------------------|------------|
|          | <b>CONSTRUCTION ITEMS</b>                     |     |     |                  |            |
| 1        | General Conditions                            | LS  | 1   |                  |            |
| 2        | Demolish Existing Equipment                   | LS  | 1   |                  |            |
| 3        | New Pump Station Complete                     | LS  | 1   |                  |            |
| 4        | Permanent Bypass Pump                         | LS  | 1   |                  |            |
| 5        | Temporary Bypass Pump and Force Mains         | LS  | 2   |                  |            |
| 6        | Precast Concrete Doghouse Manhole             | LS  | 1   |                  |            |
| 7        | Gas Detection Monitor                         | LS  | 1   |                  |            |
| 8        | Cart Path Repair                              | LS  | 1   |                  |            |
| 9        | Electrical Complete                           | LS  | 1   |                  |            |
|          | <b>EROSION CONTROL ITEMS</b>                  |     |     |                  |            |
| 10       | Construction Exit                             | LS  | 1   |                  |            |
| 11       | Silt Fence (Sdl-C) Double Row                 | LS  | 1   |                  |            |
| 12       | Disturbed Area Stabilization (D21,Ds2,Ds3,Du) | LS  | 1   |                  |            |
|          |   |     |     | <b>TOTAL BID</b> |            |

**ALL FIRMS REQUESTING TO DO BUSINESS WITH CHATHAM COUNTY MUST REGISTER ON-LINE AT [HTTP://PURCHASING.CHATHAMCOUNTY.ORG](http://PURCHASING.CHATHAMCOUNTY.ORG).**

NAME/TITLE

\_\_\_\_\_  
COMPANY NAME

\_\_\_\_\_  
ADDRESS

\_\_\_\_\_  
CITY/STATE/ZIP

\_\_\_\_\_  
PHONE NUMBER

\_\_\_\_\_  
FAX NUMBER