

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO 14-0126-4

FOR: Pavement Resurfacing of Eight County Roads

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

Responses to questions received:

Q and A

1. Q) *Will we need to tear out any concrete driveways on Lansing and Cottonvale to achieve positive drainage?*

A) No, however, if the contractor finds in his or her own layout of work that a problem with drainage exists, bring it to the Engineers attention with a proposed solution before any work is done to that area.

2. Q) *Will compaction tests be required in driveways?*

A) Compaction tests will be required per the special conditions and 1 out of every 10 driveways at the Engineers discretion.

3. Q) *If unsuitable material is determined to be in the driveways how does the County intend to handle the situation?*

A) As per GDOT Specifications Grading Complete section 210.5 C. - Undercutting areas not shown in the Plans when directed by the Engineer will be paid for at the rate of \$7.50 per cubic yard for quantities up to 750 yd³. Quantities exceeding 750 yd³ will be considered Extra Work as defined in Subsection 109.05, and will be paid for accordingly. Payment is full compensation for excavating and disposing of undesirable material and supplying, placing, and compacting replacement material.”

4. Q) *The typical section does not show prime coat to be placed nor is there a line item for bituminous prime coat. Is it safe to assume that prime coat will not be required?*

A) As per GDOT Specifications Graded Aggregate Construction section 310.3.05 E. - Apply bituminous prime according to Section 412 unless using:

Graded aggregate base under Portland cement concrete pavement

Graded aggregate base under asphaltic concrete 5 in (125 mm) or more in total thickness

GDOT Specification 310.4 B. - Bituminous prime is not measured for separate payment.

Please include the cost of the bituminous prime in your bid for GAB per the specifications keeping in mind that Section 412.3.05 says “Prime is not required on driveway construction”.


5. Q) *Is it safe to assume that temporary grassing will suffice as controlling the disturbed areas? If so, do these areas also need to be mulched or covered with straw the same day?*

A) Temporary grassing will suffice and must be planted within 7 days of disturbance. According to the GDOT Specifications Grassing 700.3.05 - Apply mulch to areas planted in temporary grass at the rate of $\frac{3}{4}$ inch to 1.5 inches.

BID OPENING REMAINS: 2PM, TUESDAY, JANUARY 6, 2015.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

12-23-14
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY