

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO BID# 19-0061-5

FOR: Indoor Pool Resurfacing at the Chatham County Aquatic Center

PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES:


1. **Question:** When the pool was originally built, was it plastered and then painted, or what is the history of the surface?
Response: The original pool surface was paint.
2. **Question:** How many times has the pool been plastered or painted?
Response: The pool was sandblasted and repainted in 2007.
3. **Question:** How many main drains are present in the bottom of each pool?
Response: The lap pool has four (4) main drains. The recreation pool has two (2) main drains.
4. **Question:** Line Item #11 says to install 2x2" unglazed red tile and sanded thin-set and white grout (SGM) to replace existing red painted striping. There was no Red painted striping observed from the pool deck. Can we get a clarification on if these are going around the lane lines, or the exact placement desired?
Response: The red lines are there but are hard to see. They are located at the 15 meter marks per USA Swimming Guidelines for long course races as well as short course races.
5. **Question:** Which emergency sensors/lights/detectors should be covered? Which HVAC duct work/access points should be covered?
Response: The four (4) motion sensors (located at each emergence exit) as well as any red siren/strobe location should be covered. The intake for the HVAC system (located under the bleachers) should have filters placed over them and checked daily for debris and replace as needed to keep flow of air to the units (during sandblasting and as dust/debris settles).

BID DUE DATE WILL REMAIN 2:00PM, JULY 02, 2019

BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES.

June 26, 2019

DATE



MARGARET H. JOYNER
PURCHASING DIRECTOR
CHATHAM COUNTY

