

CHATHAM COUNTY PURCHASING & CONTRACTING DEPARTMENT

ADDENDUM NO. 3 TO 20-0001-4

FOR: SOUTHBRIDGE INFRASTRUCTURE IMPROVEMENTS

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

Question Received:

- Q) What thickness and concrete strength is desired for the items of cart path, sidewalk, and driveway replacement?
- A) *Any concrete cart path, sidewalk, or driveway which is required to be removed to complete the work of the project shall be replaced with 5000 psi concrete with fiber. The thickness of the replacement drive will be the same as the existing item. The shape and jointing pattern (if applicable) shall be the same as the existing. All concrete removed shall be saw cut to a straight edge as directed by the County.*

BID OPENING REMAINS: 2PM, WEDNESDAY, FEBRUARY 5, 2020

THE PROPOSER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

1/29/20
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY