

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO Bid No. 11-10-6-7

FOR: Renovation of Eight Restrooms at Memorial Stadium

PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. **QUESTION:** The drawings call for removal of loose floor tile. The specifications require removal of all floor and base tile. Please clarify.

***RESPONSE:** The manufacturers of the epoxy flooring and base require a clean even substrate prior to application of the epoxy flooring and base. All floor and base tile must be removed prior to installation of the epoxy floor.*

2. **QUESTION:** Plan P200 shows new water lines to all fixtures. There are new water closets being installed on exterior walls. A new chase is not being provided for these fixtures. Installing new water piping will require extensive cutting and masonry replacement. Since these are exterior walls, we can assume that there are bond beams & that the walls may be grouted. We recommend either adding a chase wall or allow reuse of the existing water rough-ins for the Water Closets. Please advise.


***RESPONSE:** New water closets may be connected to existing cold water supply stub outs, provided that the existing supply stub out meets the provided flush valve manufacturer's specified installation dimensions. Contractor shall inspect any and all existing water supply lines that are to be reused to determine that the pipe is in serviceable condition.*

3. **CLARIFICATION:** Licensing Requirements - Either a General Contractor or Residential - Light Commercial Contractor's license is required for this project and must be part of your bid documents.

THE BID OPENING SHALL REMAIN 2PM 31 MAY 2011.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

5-27-11
DATE



WILLIAM PARSON
PURCHASING AGENT
CHATHAM COUNTY