

CHATHAM COUNTY PURCHASING & CONTRACTING DEPARTMENT

ADDENDUM NO. 1 TO 11-3-1-4

**FOR: Skidaway Road Shoulder Improvements**

---

---

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. SEE ATTACHED SHEETS (2) FOR ALL ADDITIONS, CLARIFICATIONS AND/OR CHANGES.
2. SEE ATTACHED SHEET(1) "*ATTACHMENT G " M/WBE COMPLIANCE REPORT* YOU MUST COMPLETE THIS FORM AND SUBMIT WITH YOUR BID DOCUMENTS.

NOTE: THIS WILL BE THE ONLY ADDENDUM FOR THIS PROJECT. NO FURTHER QUESTIONS WILL BE ADDRESSED.

---

---


**THE BID OPENING REMAINS: 2PM, NOVEMBER 18, 2010**

---

---

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

11-15-10  
DATE

  
\_\_\_\_\_  
ROBERT E. MARSHALL  
SENIOR PROCUREMENT SPECIALIST  
CHATHAM COUNTY

## **Skidaway Road Shoulder Improvements**

### BID ADDENDUM #1

- 1) Pay Item No. 21 Turf Establishment (Lump Sum) shall include sodding and fertilizing in accordance with GDOT standards all unpaved disturbed areas at and in front of Parcel 6 (Bridges), Parcel 7 (Barbee), Parcel 8 (Toraya), Parcel 9 (Wittfeld), and Parcel 10 (Wittfeld). The sodding shall be provided to the edge of Skidaway Road and shall be of a type consistent with and matching the turf of the individual existing lawns. No separate measurement or payment will be made for sod and fertilizer required for sod.
- 2) Installation of Structure A20 (Flaired End Section) shall include grading and removing soil from the bottom of the ditch to provide uniform and positive drainage from the upstream culvert pipe (a 30" diameter pipe, invert elevation approximately 7.0 feet, located approximately 215 feet east of A20 along Parkersburg Road). Turf shall be restored on the disturbed sides of the ditch.
- 3) Available Contractor Laydown Area

Offsite equipment parking, materials storage and contractor staging during the performance will be made available to the Contractor through a temporary easement agreement between Chatham County and the owner of property located at the southeast corner of Parkersburg Road and Lisbon Court (approximately 120 feet of frontage along Parkersburg Road), generally across the street from the Isle of Hope Elementary School. The site may be used subject to the following conditions.

1. The site shall be considered part of the project site and covered by the Contractor's insurance for this project.
2. The Contractor shall restore the ground to original or better condition, including but not limited to seeding and mulching to establish vegetative cover and grading the surface to promote positive drainage.
2. The Contractor shall surround the site with orange safety fence or as approved by the County, install all necessary devices to control sedimentation and erosion.
3. The Contractor shall protect trees and tree root zones from damage.
4. Ingress and egress from the site shall be made directly from Parkersburg Road. A construction exit (Co) per the Field Manual for Erosion and Sediment Control in Georgia shall be provided and maintained throughout the time of the project. The construction exit shall be completely removed upon project completion.
5. The contractor shall pay the County an additional \$1,000 per month or each partial month of liquidated damages if the site is not fully restored (seeded with at least 70 percent grass coverage of the ground) and all contractor equipment, materials, tools, and vehicles are not removed from the property by the date of six months following Notice to Proceed.
6. The Contractor's use of the site shall be at no additional cost to the County.

- 4) Question: It is noted on the plan profile sheets that there are Palm trees that are to be relocated but no note as to where they are to be relocated to.

Answer: The Palm trees are relocated to the station and off-set indicated. For example the note on Sheet 13.03 stating RELOCATE PALM TREE TO STA 54+43, 37.50' m LT. instructs the contractor to relocate the Palm tree indicated (pointed at) to the location indicated (STA 54+43, 37.50' left). Refer to special conditions regarding specific Palm tree relocations.

- 5) Question: Is the existing 18" RCP & Headwalls parallel to Skidaway to be removed or plugged.

Answer: Unless otherwise noted, the project includes complete removal of the exiting pipe drainage system including pipe, drain inlets and junction boxes as may be encountered along Skidaway Road. Pipe and structures not less than 12 inches from the new work and at the contractor's option may be completely filled with flowable grout material. If not removed entirely, junction boxes and drains and other structures shall be demolished to 3' below finished grade and filled with flowable grout. No additional payment shall be made for removal, grout filling or demolishing the existing piped drainage system.

**Attachment G**

**Chatham County  
Minority and Women Business Enterprise Program  
M/WBE Compliance Report**

Name of Bidder: \_\_\_\_\_

Name of Project: \_\_\_\_\_

Bid No: \_\_\_\_\_

M/WBE Firm	Type of Work	Contact Person/ Phone #	City, State	%	MBE or WBE

MBE Total \_\_\_\_\_%

WBE Total \_\_\_\_\_%

M/WBE  
Combined \_\_\_\_\_%

The undersigned should enter into a formal agreement with M/WBE Contractor identified herein for work listed in this schedule conditioned upon execution of contract with the Chatham County Board of Commissioners.

Signature \_\_\_\_\_ Print \_\_\_\_\_

Phone (    ) \_\_\_\_\_ Fax (    ) \_\_\_\_\_