

CHATHAM COUNTY PURCHASING & CONTRACTING DEPARTMENT

ADDENDUM NO. 1 TO 11-4-5-4

FOR: Pipe Remediation at Elmhurst Court


PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. SEE ATTACHED SHEET (1) FOR RESPONSES TO QUESTIONS RECEIVED.
2. REPLACE CURRENT BID SHEET WITH THE ATTACHED *REVISED* BID SHEET.

THE BID OPENING REMAINS: 2PM, DECEMBER 3, 2010.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

11-24-10
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

Bid # 11-4-5-4
Pipe Remediation on Elmhurst Court

BID ADDENDUM #1

1. Question: The trench section detail shows the bedding as flowable fill with up to the spring line with gravel above it. Is this correct?

Answer: Yes. The bottom of the pipe should be supported with blocks or other approved materials while the trench is being filled with flowable fill up to the spring line. The fill shall be allowed to set for 24 hours after pouring. During this time, Elmhurst Court is to remain open for traffic.

2. Staff added Line Item #20 on the attached revised Bid Sheet. The rip-rap blanket will be installed at the upstream headwall. It will consist of 6'-8" (1-man) stone meeting GDOT Section 805 Type 3. The rip-rap will be placed over filter fabric. Contractor shall fill the voids with flowable fill to form a hardened surface to prevent erosion.

BID SHEET

Bid Addendum #1

Pipe Remediation
 Elmhurst Court
 Chatham County, Georgia

23-Nov-10

Item #	Description	Estim. Qty.		Unit Price	Total Price
1	Grading, complete, including all project excavation/filling, finish grading, clearing, grubbing and all other removals not specifically listed, bonds, insurance and other project incidentals	1	JOB		
2	Remove unsuitable subgrade material	20	CY		
3	Foreign Borrow - Replace unsuitable subgrade or trench material only where directed by owner trench or subgrade material only where directed by owner	30	CY		
4	29" x 45" Concrete Elliptical Pipe	152	LF		
5	24" Storm Drain Pipe	14	LF		
6	Storm Manhole	2	EA		
7	Concrete Headwall	1	EA		
8	Connect to existing drainage structure	2	EA		
9	Remove and Replace Pavement	125	SY		
10	Remove and Replace Curb and Gutter	42	LF		
11	Remove and Replace Concrete Drive	35	SY		
12	Remove and Replace Fence	80	LF		
13	Remove Skid Mounted Building	1	EA		
14	Utility Coordination and Relocations	1	JOB		
15	Erosion and Sedimentation Control	1	JOB		
16	Traffic Control including Plan	1	JOB		
17	Sod	350	SY		
18	Pre-Construction Inspection with Photos	1	JOB		
19	Post-Construction Video Inspection	1	JOB		
20	Rip-Rap Blanket with flowable fill	25	SY		

TOTAL

 NAME / TITLE

 COMPANY

 ADDRESS

 PHONE/FAX NO'S.