

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO 11-0028-4

FOR: PAVING WENDY HILL ROAD

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. Rip Rap and fabric shall be placed at the pipe outlets at flared end sections A2 and A4 with five square yards at each outlet, eighteen inches deep.
2. Replace current bid sheets with the attached *revised* bid sheets (2).

THE BID OPENING REMAINS : 2PM, THURSDAY, NOVEMBER 17, 2011.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

11-14-11
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

WENDY HILL RD PAVING BID SCHEDULE

Line No.	Pay Item	Item Description	Unit	Est. of Units	Unit Price Bid	Total for Item
ROADWAY						
005	150-1000	TRAFFIC CONTROL	LS	1	\$	\$
010	207-0203	FOUNDATION BACKFILL MATL, TP II	CY	12	\$	\$
015	210-0100	GRADING COMPLETE	LS	1	\$	\$
020	310-1101	GR AGGR BASE CRS, INCL MATL	TN	320	\$	\$
025	318-3000	AGGR SURF CRS	TN	40	\$	\$
030	402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	75	\$	\$
035	413-1000	BITUM TACK COAT	GL	25	\$	\$
040	441-0016	DRIVEWAY CONCRETE, 6 IN	SY	170	\$	\$
045	441-0104	CONCRETE SIDEWALK, 4 IN	SY	3	\$	\$
050	441-9991	CONC CURB & GUTTER, 6.5 IN X 24 IN, ROLLED	LF	600	\$	\$
055	550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	180	\$	\$
060	550-4115	FLARED END SECTION 15 IN, SIDE DRAIN, 6:1 SLOPE	EA	1	\$	\$
065	550-4118	FLARED END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	3	\$	\$
070	643-8200	BARRIER FENCE (ORANGE), 4 FT	LF	240	\$	\$
075	668-2105	DROP INLET , GP 1, SPCL DESIGN	EA	1	\$	\$
PERMANENT EROSION CONTROL						
080	603-2181	STONE DUMPED RIP RAP, TYPE 3, 18 IN	SY	10	\$	\$
085	603-7000	PLASTIC FILTER FABRIC	SY	10	\$	\$
090	706-1003	TURF ESTABLISHMENT, TP C	AC	1		
095	716-2000	EROSION CONTROL MATS, SLOPES	SY	180	\$	\$
TEMPORARY EROSION CONTROL						
100	163-0232	TEMPORARY GRASSING	AC	1	\$	\$
105	163-0240	MULCH	TN	5	\$	\$
110	163-0300	CONSTRUCTION EXIT	EA	1	\$	\$

115	163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	2	\$	\$
120	163-0528	CONSTR & REMOVE FABRIC CHECK DAM, TP C SILT FENCE	LF	90	\$	\$
125	163-0550	CONSTR & REMOVE INLET SEDIMENT TRAP	EA	1	\$	\$
130	165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	1	\$	\$
135	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	1	\$	\$
140	165-0041	MAINTENANCE OF CHECK DAMS, ALL TYPES	LF	45	\$	\$
145	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	1	\$	\$
150	700-8000	FERTILIZER MIXED GRADE	TN	1	\$	\$
SIGNING AND MARKING						
155	636-1020	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 3	SF	19	\$	\$
160	636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	16	\$	\$
165	636-2070	GALV STEEL POSTS, TP 7	LF	70	\$	\$
170	653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	LF	30	\$	\$

TOTAL PRICE \$ _____

(Totals for individual items should be written out to two decimal places. Round off total price to nearest whole dollar.)

NAME / TITLE

COMPANY

ADDRESS

PHONE / FAX NO'S.

Revised bid sheet 11-14-11