

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 2 FOR BID NO. 10-7-1-3

CONTRACT TO UPGRADE CHATHAM COUNTY THUNDERBOLT
BOAT RAMP PUBLIC WORKS AND PARK SERVICES OF CHATHAM
COUNTY.

Please note the followings question was received please see both question and answer below:

1. Can the precast sections of the boat ramp slab be cast in smaller sections as opposed to the 53' x26'x8" piece as shown? Also, can this piece be set by crane? As shown, this precast piece weighs approximately 70 tons and must be pushed into place as per note 11 sheet n1.

Reply: It is recommended that the pre-cast section remains one piece and pushed into place as per the approve plan. However, the contractor can use an alternate method requiring a lower and upper pre-cast slab to lessen the weight and use a crane to set the slabs as long as the finished grade profile is maintained. Upper and lower pre-cast slabs will require stainless stell (l) bolts and shackles to connect to two pre-cast sections.

2/22/10
DATE

William R. Parson
WILLIAM R. PARSON, CPPO,
PURCHASING AGENT
CHATHAM COUNTY, GEORGIA