

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 2 TO 11-5-1-4

FOR: FENDER SYSTEM REPAIR & REPLACEMENT AT BRIDGE OVER TURNER'S CREEK ON JOHNNY MERCER BLVD.


PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

NOTE: As it pertains to the Scope of Work regarding demolition of the existing West Fender, the Contractor may, at the Contractor's discretion, remove the existing timber fender piles whole or abandon the lower portion of piles at the channel bottom or below the channel bottom, following established and standard means and methods for the removal of piles, and per GDOT specifications, where applicable. However, the Contractor shall be solely responsible removing all hazards to navigation and for removing any obstructions associated with the demolition of the existing west fender system which would hinder driving of new piles for its replacement. If the Contractor elects to abandon the ends of the piles below the channel bottom, a log shall be kept recording of all piles abandoned at the channel bottom and this log shall be submitted to the engineer during demolition phase of the project. No consideration will be given to the Contractor for delays and/or obstructions associated with these abandoned piles during the driving of the new piles.

THE BID DATE REMAINS : 2PM, WEDNESDAY JANUARY 5, 2011.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

12-30-10
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY