

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 1 TO 10-6-9-4

FOR: L. SCOTT STELL PARK BASEBALL FIELDS RENOVATIONS - PHASE II

**PLEASE SEE THE FOLLOWING ADDITIONS, CLARIFICATIONS AND/OR CHANGES
BASED ON QUESTIONS RECEIVED FROM CONTRACTORS:**

Replace current Bid Sheet with the attached *Revised* Bid Sheet (1 page)

NOTE:

- 1. Existing dugout slabs need to be removed. This shall be included in the price of the dugout removal.**
- 2. Per Chatham County, detail 29 on sheet U4, the slab thickness shall be 3 ½". Per Chatham County detail 30, on sheet U4, 6" of aggregate base is required below the dugout pads.**
- 3. Aggregate base does not apply to the dugout pads.**
- 4. Access to pour all concrete shall be from the outfields of both fields.**
- 5. Disregard Special Note #4. Fence to be installed per detail 29. Vinyl coated fencing gate detail 32 refers to all fence with the exception to wing dugout and backstop. Disregard detail 29 for height of dugout fences. Refer to sheet U1 for correct height.**
- 6. The 9 gauge is the core thickness. The vinyl coating shall be thermally fused.**
- 7. Metal roof shall be attached to 5/8" treated plywood. 5/8" treated plywood shall be attached to 2x6 pressure treated rafters @ 16" OC. Connect 2x6 rafters to double 2x8 pressure treated beams with joist hangers. Attach double 2x8 pressure treated beams to each post with (2) 3/8" galvanized carriage bolts.**
- 8. The lump sum price is to include the required portion of fence costs, plus roofs and benches. The floors for the dugouts were included in the 400 SY.**
- 9. Install 2 block scout box walls shall include costs for footings and masonry.**
- 10. A land disturbing permit is not required for this project.**

11. The Masa item #02561 or equivalent 21' bench and back shelf shall be used. Disregard the bench length shown on detail 30.

12. There is no detail of the connection of the roof to the posts and rails of the chain link dugouts. (See response #7 regarding the dugout roofs) As far as the 2x6 wood framing, a professional engineer has designed and certified that this is adequate for the intended use and the roofs shall be built per the approved plan.

THE BID OPENING SHALL REMAIN 2 PM, THURSDAY, JANUARY 28, 2010.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

1-22-10
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

BID SCHEDULE

L. SCOTT STELL PARK RENOVATIONS - PHASE II (Addendum 1 revision)

SECTION I - EARTHWORK & SITEWORK

Item No.	Description	Quantity	Units	Unit Price	Cost
1	Clearing	1	L.S.		
2	Grading	1	L.S.		
EARTHWORK AND SITEWORK SUBTOTAL:					

SECTION II - PAVEMENT

Item No.	Description	Quantity	Units	Unit Price	Cost
1	Remove 260 S.Y. of existing concrete	260	S.Y.		
2	Install 400 S.Y. of standard concrete	400	S.Y.		
PAVEMENT SUBTOTAL:					

SECTION III - DRAINAGE

Item No.	Description	Quantity	Units	Unit Price	Cost
1	Concrete Collars	24	EA.		
2	Concrete Headwalls	4	EA.		
3	Adjust Ex. 24" RCP	1	EA.		
DRAINAGE SUBTOTAL:					

SECTION IV - MISCELLANEOUS ITEMS

Item No.	Description	Quantity	Units	Unit Price	Cost
1	Remove 2500 L.F. chain link fence	1	L.S.		
2	Remove 4 wooden dugouts	1	L.S.		
3	Remove 16 light poles (Fields 1&3)	1	L.S.		
4	Remove concrete vault (Field 3)	1	L.S.		
5	Install 2800 L.F. of chain link fence	2,800	L.F.		
6	Install 2 chain link dugouts (Field 1)	1	L.S.		
7	Install 2 block dugouts (Field 3)	1	L.S.		
8	Install 2 block scout box walls	1	L.S.		
9	Install (4) 6" removable bollards	4	EA.		
MISCELLANEOUS SUBTOTAL:					

SECTION V - EROSION CONTROL

Item No.	Description	Quantity	Units	Unit Price	Cost
1	Silt Fence (Sd1-A)	2,700	L.F.		
2	Temporary Seeding (Ds1/Ds2)	17,200	S.Y.		
3	Rip-Rap (St)	71	S.Y.		
4	Retrofit (Rt)	3	EA.		
EROSION CONTROL SUBTOTAL:					

TOTAL PROJECT CONSTRUCTION COST:

NAME / TITLE

COMPANY

ADDRESS

PHONE / FAX NO'S.