

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 2 TO 10-5-1-4

FOR: KING GEORGE BOULEVARD /WILD HERON ROAD SIDEWALK EXTENSIONS

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

NOTE: Amend the sentence in Section 1 of *Special Conditions* (page 20) to read:
All materials **and products** used in the process of completion of work included in the contract will be furnished from Georgia Department of Transportation certified suppliers only. **The construction shall be done in accordance with the standards and specifications provided for this project as well as the ADA Standards for Accessibility, Appendix A, Part 36.**


Questions / Responses:

1. The Measurement & Payment sections for Phase 1-A and Phase 1-B in the specs call for expansion joints every four feet. The plans call for expansion joints a minimum of every 80 feet. Are the joints every four feet the sidewalk contraction joints that can be formed or sawed?
 - **Yes, every 4' there shall be a contraction joint that can be formed or sawed. Expansion joints shall be 1/2" pre-formed fiberboard and every 80'.**
2. The plans call for contraction joints that are 3/4" deep. Specification section 02520, paragraph 3.05 C, calls for control joints with a depth of 1/3 of the thickness of the concrete. Which is the preferred depth of control joints in the sidewalk?
 - **Control joints shall be 3/4" deep.**
3. In spec section 02520, paragraph 3.07 A, both curing compound and curing paper are to be used. Is one or the other acceptable, or does the County want both curing systems applied?
 - **Just the compound will be sufficient. It shall conform to ASTM C309.**

THE BID OPENING REMAINS: 2PM, TUESDAY, DECEMBER 15, 2009.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

12-10-09
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY