

CHATHAM COUNTY PURCHASING DEPARTMENT

ADDENDUM NO. 5 TO BID NO. 15-0016-4

FOR: CHATHAM COUNTY FUEL STATION

PLEASE SEE THE FOLLOWING FOR ADDITIONS, CLARIFICATIONS AND/OR CHANGES:

1. Replace current Bid Sheets (2 pages) with the attached REVISED Bid Sheets (2 sheets).

2. Response to questions received:

Q) Which line item should we put the landscaping in?

A) *A revised bid sheet is included with this addendum which includes a line item for "Landscaping - Complete".*

Q) On General Planting/Irrigation Notes on Page LS2.1, #22 it states contractor to supply automatic irrigation system. Will there be a plan provided for that layout, or are we to design the layout and system?


A) *No plan will be provided. Contractor is to design the irrigation system and submit to the engineer for review as a shop drawing prior to installation. All costs associated with the design, permitting and installation shall be included in the contract lump sum price for "Landscaping - Complete".*

NOTE: THIS WILL BE THE FINAL ADDENDUM FOR THIS PROJECT.

THE BIDDER IS RESPONSIBLE FOR MAKING THE NECESSARY CHANGES AND MUST ACKNOWLEDGE RECEIPT OF ADDENDUM.

THE BID OPENING REMAINS : 2:00 PM, APRIL 2, 2015

3/30/15
DATE



ROBERT E. MARSHALL
SENIOR PROCUREMENT SPECIALIST
CHATHAM COUNTY

CHATHAM COUNTY FUEL STATION
CHATHAM COUNTY BOARD OF COMMISSIONERS

BID FORM

| ITEM | DESCRIPTION | QUANTITY | | COST | |
|---|--|-----------------|--------------|----------|------------|
| | | NUMBER OF UNITS | UNIT MEASURE | PER UNIT | TOTAL COST |
| WATER DISTRIBUTION SYSTEM | | | | | |
| 1 | Connect to Existing 8" Water Main | 1 | ea | | |
| 2 | 8" PVC Water Main - C900 - DR18 | 405 | lf | | |
| 3 | 6" PVC Water Main - C900 - DR18 | 173 | lf | | |
| 4 | 4" PVC Water Main - C900 - DR18 | 169 | lf | | |
| 5 | 1" Water Service Lateral | 100 | lf | | |
| 6 | 8" Tapping Sleeve & Valve | 1 | ea | | |
| 7 | 8" Gate Valve & Manhole | 1 | ea | | |
| 8 | 6" Gate Valve & Manhole | 1 | ea | | |
| 9 | 4" Gate Valve & Manhole | 1 | ea | | |
| 10 | Fillings | 1305 | lb | | |
| 11 | 6" Post Indicator Valve | 1 | ea | | |
| 12 | Fire Hydrant Assembly | 1 | ea | | |
| 13 | 1" Frost-Proof Hydrant | 1 | ea | | |
| 14 | 6" RPZ | 1 | ea | | |
| 15 | 4" RPZ | 1 | ea | | |
| 16 | 4" Meter | 1 | ea | | |
| WATER DISTRIBUTION SYSTEM SUBTOTAL | | | | | |
| GRADING & DRAINAGE | | | | | |
| 1 | Clearing and Grubbing | 1.07 | ac | | |
| 2 | Grading | 5200 | sy | | |
| 3 | Unsuitable Material | 1800 | cy | | |
| 4 | Borrow | 2100 | cy | | |
| 5 | Curb Inlet - Type B | 1 | ea | | |
| 6 | Grate Inlet (4'x4') | 4 | ea | | |
| 7 | Grate Inlet (4'x4') w/ Baffle | 1 | ea | | |
| 8 | 18" RCP | 350 | lf | | |
| 9 | 24" RCP | 58 | lf | | |
| 10 | 18" Flared End Section | 1 | ea | | |
| 11 | 24" Flared End Section | 1 | ea | | |
| 12 | Control Structure No.1 | 1 | ea | | |
| 13 | Rip-Rap | 15 | sy | | |
| GRADING & DRAINAGE SUBTOTAL | | | | | |
| EROSION & SEDIMENTATION CONTROL | | | | | |
| 1 | Gravel Construction Exit | 1 | ea | | |
| 2 | Silt Fence (incl Maintenance) | 1405 | lf | | |
| 3 | Filter Ring (incl Maintenance) | 2 | ea | | |
| 4 | Inlet Sediment Filter | 8 | ea | | |
| 5 | Tree Protection Fence | 86 | lf | | |
| 6 | Temporary Grassing | 6400 | sy | | |
| 7 | Permanent Grassing | 3460 | sy | | |
| EROSION & SEDIMENTATION CONTROL SUBTOTAL | | | | | |
| PAVING | | | | | |
| 1 | 8" Reinforced Concrete Paving | 2810 | sy | | |
| 2 | 4" GABC | 2882 | sy | | |
| 4 | 30" Curb & Gutter | 53 | lf | | |
| 5 | 8" Concrete Valley Gutter | 72 | sy | | |
| 6 | Integral Curb, TP2 | 438 | lf | | |
| 7 | Exist. Asphalt Paving Remove & Replace | 200 | sf | | |
| PAVING SUBTOTAL | | | | | |

CHATHAM COUNTY FUEL STATION
CHATHAM COUNTY BOARD OF COMMISSIONERS

BID FORM

| ITEM | DESCRIPTION | QUANTITY | | COST | |
|--|--|-----------------|--------------|----------|------------|
| | | NUMBER OF UNITS | UNIT MEASURE | PER UNIT | TOTAL COST |
| TRAFFIC CONTROL, SIGNING & MARKING, FENCING, LANDSCAPING | | | | | |
| 1 | Traffic Control | 1 | ls | | |
| 2 | Stop Sign | 1 | ea | | |
| 3 | 24" White Thermoplastic Stop Bar | 20 | lf | | |
| 4 | Steel Bollards | 12 | ea | | |
| 5 | Chain Link Fence - 8'H, Black PVC Coated | 340 | lf | | |
| 6 | Masonry Column | 6 | ea | | |
| 7 | Landscaping - Complete | 1 | ls | | |
| 8 | Rolling Gate - Complete | 1 | ls | | |
| TRAFFIC CONTROL, SIGNING & MARKING, FENCING, LANDSCAPING SUBTOTAL | | | | | |
| PROJECT TOTAL | | | | | |

 NAME / TITLE

 COMPANY

 ADDRESS

 PHONE / FAX NO'S.

 E-MAIL